

Project Profile

Summit Road/Glenn Street Water Main Replacement



Year:
2010-2011

Client:
City of Barberton

Location:
Summit Road and Glenn
Street, Barberton and
Norton, Ohio

Project Scope:

The project consisted of the replacement of 7,200 feet of an existing 24" water main with a new 24" water main, fire hydrants, valves, service connections, connections to the existing 24" main with cut-in tee, connections to the existing 6" and 8" mains (side streets), pavement and drive restoration, lawn restoration, and other appurtenances.

Project Services:

- Provided Construction Engineering services.
- Provided Inspection Services.
- General project oversight for contract compliance.
- Managed and tracked pay items, produced payment requests, Answered requests for information, reviewed and analyzed requests for extra costs, conducted inspections and provided deficiency lists and final punch list.
- Provided close-out package to owner with photographs and contract information.

Cost:
\$1.7 M